

A 1065


FRONT VIEW

NOTES:

- 1. ALL EQUIPMENT SHALL BE INSTALLED IN APPROXIMATE LOCATIONS AS SHOWN IN THE DRAWING
- 2. ALL EQUIPMENT SHALL BE MOUNTED ON OR SUPPORTED BY VIBRATION INSULATOR OR ASSEMBLIES
- 3. ALL PIPING SHALL BE LEAK TESTED WITH A PRESSURE OF AT LEAST 1 $\frac{1}{2}$ TIMES THE DESIGN WORKING PRESSURE.
- 4. ALL MATERIALS TO BE USED SHALL BE NEW AND CLEAN
- 5. ALL INSTALLATION WORK SHALL BE DONE IN A NEAT AND WORKMAN LIKE MANNER
- 6. ALL WORKS SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR AFTER DATE ACCEPTANCE







SIDE VIEW

SPECIFICATIONS						
UNIT NAME	FWMT05CV1					
QUANTITY	20					
COOLING CAP.	4.5 kW					
POWER SOURCE	220V/1 PH/50 HZ					
AIR FLOW (CFM)	450					
FAN SPEED (RPM)	920 RPM					
FAN MOTOR						
RATED INPUT POWER (W)	50					
RATED INPUT CURRENT (A)	0.29					
MOTOR OUTPUT (W)	26					
COIL	7 MM COPPER					

1	WALL MOUNTED FAN	COIL DETAILS
-	SCALE	NTS

ı		
	RatState II	F
	BATANGAS STATE UNIVERSITY Gov. Pablo Borbon Main Campus II Alanailan, Batangas City	
	MECHANICAL ENGINEERING DEPARTMENT	F

_	PROJECT LEADER	INSTRUCTOR		PROJECT / LOCATION:	OWNER	PREPARED BY:	No.	REVISIONS	DATE	CLIEFT CONTENT	SHEET NO.
I							1	DRAWING DETAILS	12/10/2019	SHEET CONTENT	SHEET NO.
)	ENGR. MARK KERVIN N. ABU MECHANICAL ENGINEER	ENGR. ALLAN B. DE VILLA PROFESSIONAL MECHANICAL ENGINEER	PROPOSED THREE STOREY HOSPITAL	L TEAM ABU	ABU, MARK KERVIN N.	2	DRAWING DETAILS	12/22/2019	WALL MOUNTED FCU DETAILS	M	
·											
: II					AZUCENA, RONIEL A.					(IVI	
tv	SECTION: ME - 5103	PRC Reg No.	PTR No.			AZOCENA, NONIEL A.					\ 27 /
NT	GROUP NO: 12	TIN:	Issued on:	BATANGAS CITY	ENGR. RONIEL A. AZUCENA PRESIDENT	CASTILLO, JOHN ADRIAN M.					
	DATE SUB: DECEMBER 22, 2019		Issued at:	BATANGAS CITY							